EMMA RF System Andrew Moss ASTeC, Daresbury Laboratory



18th September 2009

RF Overview

Andrew Moss

Content



- EMMA Project Overview
- ALICE
- EMMA Equipment General
- EMMA RF System Overview
 - Cavity Design
 - Waveguide Distribution
 - Power Source
- LLRF
 - Tasks for LLRF
 - Tests at Daresbury
 - EMMA start up
- Schedule
- Conclusion

BASROC and CONFORM



- British Accelerator Science and Radiation Oncology Consortium
- BASROC is an umbrella group of academic, medical and industry specialists in accelerator and medical technology with the aim of promoting the use of accelerators in science, industry and medicine. More detail at <u>www.basroc.org.uk/</u>
- BASROC will sponsor and provide oversight to projects, such as the CONFORM Project





- EMMA is using the ALICE as the injector (Accelerators and Lasers In Combined Experiments)
- Electron Model for Many Applications
- Part of a larger Project called CONFORM (COnstruction of a Nonscaling FFag for Oncology, Research, and Medicine) <u>www.conform.ac.uk/</u>
- 3 parts to the project are funded
 - EMMA design and construction
 - PAMELA design study funding £865k
 - Applications study funding £273k
- Total funds for EMMA are £5.75m over 3.5 year project lifecycle

EMMA Collaboration



ASTeC

- STFC recognise and appreciate the active collaboration from:
 - Brookhaven National Laboratory
 - CERN
 - Fermi National Accelerator Laboratory
 - Laboratoire de Physique Subatomique et de Cosmologie
 - Science & Technology Facilities Council UK
 - John Adams Institute UK
 - Cockcroft Institute UK
 - TRIUMF

.

 Technical presentations stored on the CONFORM web server at <u>https://www.conform.ac.uk/documents/emma/ec%20-</u> <u>%20emma%20collaboration%20meetings/</u>

Motivation for constructing EMMA



ASTeC

Muon Acceleration



THE INTERNATIONAL DESIGN STUDY FOR THE NEUTRING FACTORY

– Muon Sources



18th September 2009

Proton & Carbon Therapy



Energy & Environment





Aims & Objectives of EMMA Project

- Prove that a NS-FFAG can successfully accelerate particles – EMMA is a proof of principle demonstration
 - Study linear non-scaling FFAGs under particular circumstances
 - Rapid acceleration
 - Relativistic energies
 - Two important characteristics of non-scaling FFAG lattices
 - Rapid acceleration through many resonances
 - Unique longitudinal dynamics



- To test our understanding of the underlying dynamics
 - How does emittance growth depend on which resonances we cross?
 - How does longitudinal behaviour change with machine parameters
 - RF frequency
 - Energy where machine is isochronous
 - Coupling of transverse and longitudinal motion
 - What effect do errors have on performance
 - Magnet position
 - Field strength
 - RF phase errors

Accelerators and Lasers In Combined Experiments (ALICE)



| Parameter | Value | |
|-----------------------|---------------------|--|
| Nominal Gun Energy | 350 keV | |
| Max. Booster Volts | 8 MV | |
| TL 2 Energy | 8.33 MeV | |
| Max. Linac Volts | 26.67 MV | |
| Max. Energy | 35 MeV | |
| Linac RF Frequency | 1.300 GHz | |
| Bunch Repetition Rate | 81.25 MHz | |
| Bunch Spacing | 12.3 ns | |
| Max Bunch Charge | 80 pC | |
| Particles per Bunch | 5 x 10 ⁸ | |

Andrew Moss

ASTeC

RM

ALICE





18th September 2009

RF Overview

Andrew Moss

ALICE



ASTeC



18th Septernber 2009

RF Overview

Andrew Moss





- Low noise Wenzel oscillator 10Mhz in, 81.25Mhz and 1.3Ghz out
- Rossendorf analog LLRF cards running in pulsed mode at 1-20Hz 4

 20mS
- 3 different types of IOTs power ALICE SC Tesla type cavity's
 - 2 e2v IOT's combine to give 32kW booster 1
 - CPI 21kW IOT booster 2
 - e2v 16kW IOT linac 1
 - Thales 16kw IOT linac 2
- ALICE has been in operation for 1 year with electron beam
- Energy recovery achieved, work on Terra-Hertz and Compton Back Scattering continuing, FEL being installed

EMMA Layout & Basic Parameters





ASTeC

BASROC







ASTeC



RF Overview





ASTeC



RF Overview





Diagnostic Phase Line 1





Diagnostic Phase Line 2



BASROC

EMMA RF Specification

Machine Parameters Value 1.3 Frequency (GHz) **Number of Straights** 21 Number of Cavities 19 Total Acc per turn 2.3 MV Upgrade Acc per turn 3.4 MV **Beam Aperture** 40mm **RF Bunch Length** 1.6 ms 5 -20 Hz **RF** Repetition rate **Phase Control** 0.3 D **Amplitude Control** 0.3 %



ASTeC



18th September 2009

RF Design

- Voltage:
 - 20 120 kV/cavity essential, based on 19 cavities
 - Up to 180 kV/cavity desirable
- Frequency:
 - 1.3 GHz chosen, to both match the ALICE RF systems and also allow for the use of developed and mature LLRF systems at this frequency
 - Range requirement 5.6 MHz
- Cavity phase:
 - Remote and individual control of the cavity phases is essential



| Cavity Design | |
|---------------|--------------------------|
| 110 mm | |
| | |
| | Input coupling loop |
| | Coolant channels |
| | Aperture Ø 40 mm |
| | Probe |
| | Capacitive post tuner |

Normal conducting single cell re-entrant cavity design optimised for high shunt impedance

18th September 2009

RF Overview



| Parameter | Value | |
|---|----------------|--------|
| Frequency | 1.3 GHz | |
| Theoretical Shunt Impedance | 2.3 MΩ | |
| Realistic Shunt Impedance (80%) | 2 Μ Ω | |
| Qo | 20,400 | |
| R/Q | 100 Ω | |
| Tuning Range | -4 to +1.6 MHz | |
| Accelerating Voltage | 120 kV | 180 kV |
| Total Power Required (Assuming 30% losses in distribution | 90 kW | 200 kW |
| Power required per cavity | 3.6 kW | 8.1 kW |

Cavity manufacture



Cavity construction **NIOWAVE, INC.**



ASTeC

- All cavities now received
 - Final 4 awaiting input couplers from Times Microwave
 - 2 input couplers have been delivered
- Input couplers
 - Leaks discovered on 2 of the feedthroughs
 - Poor response from Times Microwave
 - Alternatives from SLAC or Niowave being sought
- Cavity evaluation
 - Four cavities successfully conditioned
 - Q₀≈20000 achieved
 - Crosstalk seen on the pick-up probe
 - Responses to be checked and coupler to be adjusted by 180 degrees

18th September 2009

RF Overview





18th September 2009

RF Overview

Andrew Moss



•The same regardless of number of splits.

•Compact System





- Power split from the IOT with a 3dB hybrid
 - 10 RF cavities anti-clockwise
 - 9 RF cavities clockwise
- Amplitude control
 - RF power from the IOT
 - Cavity frequency
- Phase control
 - Cable length (fixed)
 - Phase shifter
- Complete system undergoing final tests
 - 3dB hybrid required
 - No flexible waveguide sections
 - Straight length of WR650 still to be defined







Waveguide test assembly at Qpar Angus CONFORM



18th September 2009

RF Overview

Andrew Moss

RF Power amplifier

- Contract placed with CPI for supply of the RF source
- VIL409 high power RF amplifier system in 3 racks
- A single 100kW (pulsed) IOT supplying the 19 RF cavities distributed around EMMA
- Utilises a Bruker solid state amplifier up to 1.8kW
- Similar unit to that already being used on ALICE but with a larger bandwidth
- Software and system tests are in progress
- Delivery immanent







ASTeC





- LLRF system needed to stabilise the amplitude and phase of 19 cavities to 0.3% and 0.3 degrees
- ALICE will be operated in single bunch mode,1 to 20 Hz to inject into EMMA at 10mEV
- EMMA requires ability to run over frequency variation +1.5 to 4Mhz from 1.3GHz while maintaining synchronisation with ALICE bunch timing
- LLRF system has the task of generating the frequency offset the operators pick, then tuning the cavity's to the correct frequency and setting the waveguide phase shifters to correct for phase length errors
 - It is expected this that this process will need to be done daily

LLRF decisions



- The LLRF system is unusual due to the need to vary the frequency of the machine while maintaining synchronisation with the injector at a fixed frequency
- However the topology suits a vector sum layout used at many accelerator machines
- A tender for the LLRF system was released and a number of proposals where received leading to the option to purchase the I Tech Libera system

LLRF test layout



ASTeC



18th September 2009

RF Overview

LLRF 'network analysis mode'

- Testing of a prototype Libera LLRF system using two EMMA cavities, Qpar hybrid splitter and phase shifter to simulate conditions on the EMMA machine
- Intial 'network analysis' mode of Libera showed problems with cavity response



ASTeC

BASROC

RF Overview

Clean room checks

- In the clean room cavity's were checked with a Network Analyser
- Showed over coupling of the field probe
- Field probe was rotated 180 degrees
- All 19 cavity's have now been changed to give the correct response



Andrew Moss

LLRF high power tests in to cavity

- Frequency sweep mode used to tune cavity frequency
- Double hump found in response
- Eventually traced to interaction between the cavitys and the output of the IOT (itself a cavity)
- Inclusion of a circulator on the output of the IOT resolved this
- Performance achieved at 5kW (~150kV) per cavity
 - Phase: 0.0093° (spec is 0.3°)
 - Amplitude: 0.006% (spec is 0.3%)





ASTeC

BASROC

SCRF test

- During tests of EMMA cavities, two SC 3.9Ghz ILC crab cavities were cold in our vertical test stand
- 2 hour 'window' to test
- Libera system had front end components changed and then was connected and setup within 1 hour to perform first test on SCRF
- Phase locked across the cavitys
- No microphonics compensation at that time, however system was very stable
- Impressive !





RF Overview

Andrew Moss





EMMA Set up procedure



- Initial Set-Up
 - No beam
 - Low power mode Cavities tuned to resonant frequency
 - Phase shifters adjusted to give desired phase map
- RF Power Set-Up
 - No beam
 - Desired output power from IOTs set
 - Determined by the power for the 10 cavities
 - Amplitude adjusted and locked
 - Detune the 9 cavity section
 - Phases adjusted and locked
 - Apply beam
 - Beam loading negligible

18th September 2009

Set up continued



- Phase Adjustment
 - RF system is phase locked to the master oscillator at 1.3Ghz
 - Injection phase control is a matter of setting a fixed offset between the master oscillator and the cavity vector sum.
 - All cavity phases will be referenced to a defined cavity
- However when the EMMA frequency is changed the synchronisation with the injector must be maintained
- Working towards a good solution with ITech

Schedule



- The EMMA machine is currently being installed into the experimental hall
 - Cavitys and magnet components are installed on machine support girders
 - Waveguide system has arrived on site
 - RF power supply is having acceptance test in USA this week
 - LLRF system is on site awaiting installation
- Components will be installed during a 3 week shutdown during October
- Beam tests will begin in November 09





- The EMMA machine is a novel exciting project, rapid acceleration is interesting to many fields of accelerator design
- The RF system is complex in layout and in some ways unusual
- We know the LLRF system will provide us with many diagnostics and aid us in the operation of the machine
- It is perhaps very wise that we have chosen a LLRF system that is so flexible, which can be developed and changed to meet new challenges as they are found, extremely important in this machine